DEPARTMENT OF PUBLIC WORKS
815-724-4200 Direct
815-723-7770 Fax
Email: dortiz@joliet.gov

CITY OF JOLIET

150 WEST JEFFERSON STREET
JOLIET, ILLINOIS 60432-4158

CITY OF JOLIET

AUGUST 18, 2022

ADDENDUM NO. 1

TO: **DEKALB STREET/ DORA AVENUE ROADWAY PROJECT – MFT SECT. NO. 22-00549-00-FP**

THE ATTENTION OF ALL PROSPECTIVE BIDDERS ON THE ABOVE REFERENCED PROJECT IS CALLED TO THE FOLLOWING LISTED MODIFICATION IN THE CONTRACT DOCUMENTS:

1. Attached are the revised schedule of prices on form BLR 12201. Please remove the existing schedule of prices and insert the revised schedule of prices with "(printed 8/18/22)" note at bottom left corner of pages.
2. Quantities have been corrected.
3. The mailboxes shall be relocated to behind the sidewalk on the east side of the roadway on Dora Ave. and paid for per item #52.
4. Item #62 has been changed to Storm Sewer, Ty 1 RCCP, CL IV 15". This storm sewer shall be placed Dora Ave. from manhole #2 to existing manhole at Sta 6+02 at the proposed inverts shown on plans for the existing manhole and manhole #2.
5. Item 62 shall be used to cut the existing concrete pavement at DeKalb & Center to be removed in addition to cut the pavement per City of Joliet Special Provision #442.10.
6. Fire Hydrant at Dora & Woodruff shall be moved to 2' behind the proposed curb & gutter. The valve shall not be relocated. This work will be paid for per Item 63 and shall be performed per City of Joliet Special Provision #564.00 (attached).
7. The Dora Ave. plans show incorrectly the exiting storm sewer as 15" from Sta. 5+68 to Sta. 6+02. The existing storm sewer from Sta. 5+68 to Sta. 6+02 is 12" and shall be removed. Work is to be performed per City of Joliet Special Provision #551.00 (attached) and paid for per Item 64.

The Acknowledgement of the Receipt of all Addendums must be printed clearly on the outside of your Bid Package or your Bid may not be opened.

551.00 STORM SEWER REMOVAL

This work includes furnishing all materials, equipment and labor necessary to remove storm sewer in accordance with Section 551 of the "Standard Specifications". This work shall also include plugging the existing drainage structure which shall remain in place after this storm sewer has been removed from it. The existing remaining drainage structure shall be plugged with brick and mortar to the satisfaction of the Engineer and this work shall be considered incidental to the storm sewer removal.

Basis of Payment:

This work will be paid for at the contract unit price per linear foot for STORM SEWER REMOVAL, of the diameter specified, measured as removed.

564.00 FIRE HYDRANTS TO BE MOVED

This item shall be in accordance with the applicable portions of Section 564 of the "Standard Specifications."

Hydrants shall be located a minimum of two (2) feet behind back of curb in locations determined on the plans or by the resident Engineer. They shall be plumb and shall be set so that the lowest hose connection is at least eighteen (18) inches above the surrounding finished grade and that the 'break-away' connection is no more than three inches (3") above the finished ground surface. Ductile iron 'offset fittings', or approved equal, shall be used to make final adjustments.

A minimum of a 1/4 cubic yard of course stone shall be placed at and around the base of the hydrant to insure proper drainage of the hydrant after use. Care shall be taken to ensure that weep holes are not covered by concrete. The hydrant shall be set on a concrete block to ensure a firm bearing for the hydrant base. The resetting of existing hydrants and moving and reconnections of existing hydrants shall be handled in a manner similar to a new installation.

Watermain extensions shall be made with Iron Pipe Class 52 in accordance with AWWA C151, and with set screw-type retainer glands on all mechanical joints in accordance with AWWA C153. Tyler 5-158 MJX Flange Adapters should be used when connecting to existing flanged auxiliary valve. Tie rods, friction clamps, ductile lugs or other restraint systems approved by the Engineer, must be used to restrain **all existing pipe joints between the hydrant and the tee including the valve and the tee**. This restraining system shall be installed prior to making the vertical and/or horizontal adjustment to the fire hydrant. All fittings (including tie rods, friction clamps, or other restraint systems), ductile iron pipe and stone required to complete this work shall be included in the unit price to move the hydrant. The City will not shut off the water main unless the auxiliary valve cannot provide a sufficient shut off to perform the work.

Basis of Payment:

This work will be paid for at the contract unit price each for FIRE HYDRANTS TO BE MOVED. All fittings required to complete this work shall be included in the unit price to move the fire hydrant.

Illinois Department of Transportation

Schedule of Prices

Contractor's Name

Contractor's Address | City | State | Zip Code

Local Public Agency | County | Section Number

CITY OF JOLIET | Will | 22-00549-00-FP

Route(s) (Street/Road Name)

DEKALB/ DORA

Schedule for Multiple Bids

Combination Letter	Section Included in Combinations	Total

Schedule for Single Bid

(For complete information covering these items, see plans and specifications.)

Item Number	Items	Unit	Quantity	Unit Price	Total
1	TREE ROOT SAWING	EA	13		
2	PARKWAY EXCAVATION	SQ YD	1900		
3	ROADWAY EXCAVATION	CU YD	1072		
4	ROCK EXCAVATION	CU YD	120		
5	REM & DISP UNSUIT MAT	CU YD	160		
6	REM & DISP CONT MAT	CU YD	25		
7	TRENCH BACKFILL	CU YD	110		
8	AGG BASE CSE B, 8"	SQ YD	2835		
9	SUB GRAN MAT C 3"	SQ YD	560		
10	PREPARATION OF BASE	SQ YD	2380		
11	AGG BASE REPAIR	TON	100		
12	POROUS GRAN EMB SPEC	CU YD	160		
13	ST SWR, T-1 RCCP CL IV, 12"	LIN FT	186		
14	ST SEWER, DIP CL 52, 12"	LIN FT	90		
15	ROCK EX FOR STRUCT	CU YD	20		
16	INLET T-A W/ TY 11F&G	EA	2		
17	INLET T-A W/ TY 3 F&G	EA	1		
18	INLET T-A W/ TY 9 F&G	EA	1		
19	CB, TY C W/T11 F&G	EA	1		
20	CB, TY C W/T11 F&G -SPEC	EA	1		
21	MANHOLES, TY A 4' DIA	EA	2		
22	FR & LIDS, TY1CL	EA	1		
23	CB TO BE RELOCATED	EA	1		
24	COM CC&G TB6.12	LIN FT	2120		
25	COMB CC&G TB6.18	LIN FT	25		

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
CITY OF JOLIET	Will	22-00549-00-FP	DEKALB/ DORA

Item Number	Items	Unit	Quantity	Unit Price	Total
26	COM CC&G TB6.24	LIN FT	30		
27	BARRIER CURB	LIN FT	145		
28	COMB CURB & GUTTER REM	LIN FT	150		
29	SIDEWALK REMOVAL	SQ FT	1600		
30	LATE SIDEWALK REM	SQ FT	100		
31	PCC DRIVEWAY PAVT 6"	SQ YD	155		
32	PCC DRIVEWAY PAVT 8"	SQ YD	50		
33	PCC SIDEWALK 5"	SQ FT	1790		
34	PCC PAVE R&R, 10"	SQ YD	22		
35	HMA DRIVEWAY PAVT 3"	SQ YD	160		
36	HMA R&R, 4"	SQ YD	10		
37	HMA R&R, 6"	SQ YD	20		
38	TOPSOIL F & P 3	SQ YD	1900		
39	SODDING	SQ YD	1900		
40	TEMPORARY DW ACCESS	TON	30		
41	TRAFFIC CONTROL & PROT	L SUM	1		
42	SAWCUT ASPHALT SURF	LIN FT	270		
43	SAWCUT CONCRETE SURF	LIN FT	150		
44	PROTECTIVE COAT	SQ YD	925		
45	DETECTABLE WARNING	SQ FT	32		
46	CONC DRIV PAVEMENT REM	SQ YD	80		
47	MANHOLE TO BE RECONST	EA	4		
48	EROSION CONTROL	L SUM	1		
49	HARDWOOD MULCH	EA	13		
50	SLOPEWALL, 4"	SQ FT	30		
51	REMOVE & REPL HANDHOLE	EA	1		
52	MAILBOX PROT/RELOCAT	EA	4		
53	RELOCATE FH W/ AUX VALV	EA	1		
54	ADJ WATER SERVICE LINES	LIN FT	20		
55	SAN SERVICE REPL CASE I	LIN FT	10		
56	SAN SERVICE REPL CASE II	LIN FT	20		
57	DOMESTIC WATER SER ADJ	EA	7		
58	DOMESTIC WATER SER REL	EA	3		
59	CB, TY C W/T11V F&G	EA	2		
60	SS, TY 1 RCCP, CL IV 15"	LIN FT	34		
61	INLET, TY A, W TY 11V F&G	EA	1		
62	SAWCUT	LIN FT	70		
63	FIRE HYDRANT TO BE MOVE	EACH	1		
64	REMOVE STORM SEWER, 12"	LIN FT	38		
				Bidder's Total Proposal	

1. Each pay item should have a unit price and a total price.
2. If no total price is shown or if there is a discrepancy between the product of the unit price multiplied by the quantity, the unit price shall govern.
3. If a unit price is omitted, the total price will be divided by the quantity in order to establish a unit price.
4. A bid may be declared unacceptable if neither a unit price or total price is shown.