DEPARTMENT OF
PUBLIC WORKS
815-724-4200 Direct
815-723-7770 Fax

CITY OF JOLIET

150 WEST JEFFERSON STREET
JOLIET, ILLINOIS 60432-4158

April 13, 2023

CITY OF JOLIET

ADDENDUM NO. 1

TO: PROSPECTIVE BIDDERS FOR THE GARDEN STREET (W. OF KELLOGG STREET) CULVERT REPAIR PROJECT - 2023
CONTRACT No. 2719 - 0523

THE ATTENTION OF ALL PROSPECTIVE BIDDERS ON THE ABOVE REFERENCED PROJECT IS CALLED TO THE FOLLOWING LISTED MODIFICATION IN THE CONTRACT DOCUMENTS:

1. Pay Item # 10 "STORM SEWER 15" CMP RECONNECTION" has been revised to a unit of "EACH".

The existing 15" CMP connection to the existing Elliptical CMP Storm Sewer is a blind connection. The "Each" Unit Price for the Blind Reconnection shall consist of providing all material, labor, and equipment necessary to reconnect the existing 15" CMP to the new Elliptical CMP Storm Sewer.

2. A revised SCHEDULE OF PRICES is included with this addendum # 1.

THE ACKNOWLEDGEMENT OF THE RECEIPT OF ALL ADDENDUMS MUST BE PRINTED CLEARLY ON THE OUTSIDE OF YOUR BID PACKAGE OR YOUR BID MAY NOT BE OPENED.

Mark S. Sefcik

Mark S. Sefcik
Civil Engineer I
Phone: (815) 724-4210
Fax: (815) 723-7770

ADDENDUM # 1

17. The undersigned submits herewith his schedule of prices covering the work to be performed under this contract.

CITY OF JOLIET

GARDEN STREET (W. OF KELLOGG STREET) CULVERT REPAIR PROJECT - 2023

SCHEDULE OF PRICES

(FOR MORE INFORMATION REGARDING THESE ITEMS SEE PLANS AND SPECIFICATIONS)

ITEM #	ITEM DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	COST
1	TREE ROOT SAWING	2	EACH		
2	PARKWAY EXCAVATION	325	SQ YD		
3	TRENCH BACKFILL	150	CU YD		
4	AGGREGATE BASE COURSE TYPE B 8"	425	SQ YD		
5	STONE RIPRAP, CLASS A3	185	SQ YD		
6	STORM SEWER REMOVAL, 28" x 42" ELLIPTICAL CMP	220	LIN FT		
7	STORM SEWER REMOVAL, 35" x 48" ELLIPTICAL CMP	110	LIN FT		
8	36" ELLIPTICLE CMP STORM SEWER, 29" x 42" 16 (gauge)	220	LIN FT		
9	42" ELLIPTICLE CMP STORM SEWER, 33" x 49" 16 (gauge)	110	LIN FT		
10	STORM SEWER 15" CMP RECONNECTION	1	EACH		
11	DRIVEWAY PAVEMENT REMOVAL & REPLACEMENT	45	SQ YD		
12	DITCH GRADING	85	SQ YD		
13	FURNISHING AND PLACING TOPSOIL	195	SQ YD		
14	SODDING	195	SQ YD		
15	TRAFFIC CONTROL AND PROTECTION	1	L SUM		
16	SAWCUT ASPHALT SURFACE	125	LIN FT		
17	HMA REMOVAL & REPLACEMENT 4", 2 1/2" BINDER & 1 1/2" SURFACE	425	SQ YD		
18	TEMPORARY DRIVEWAY ACCESS	25	TON		
19	ALL SITE RESTORATION (MAILBOX RESET, REPLANT FLOWERS, etc.)	1	L SUM		
20	EROSION CONTROL	1	L SUM		
				BIDDER'S PROPOSAL FOR MAKING THE IMPROVEMENTS	

BIDDER'S NAME _____

CONTACT PERSON _____

BIDDER'S EMAIL ADDRESS _____