DEPARTMENT OF PUBLIC WORKS
815-724-4200 Direct
815-723-7770 Fax
Email: dortiz@joliet.gov

CITY OF JOLIET

150 WEST JEFFERSON STREET
JOLIET, ILLINOIS 60432-4158

CITY OF JOLIET

AUGUST 22, 2023

ADDENDUM NO. 1

TO: **JOLIET ST/ OTTAWA ST STREETSCAPE IMPROVEMENTS PROJECT**
CONTRACT NO. 2744-0923

THE ATTENTION OF ALL PROSPECTIVE BIDDERS ON THE ABOVE REFERENCED PROJECT IS CALLED TO THE FOLLOWING LISTED MODIFICATION IN THE CONTRACT DOCUMENTS:

The parking meter post on Scott St. next 150 N Ottawa St. is to be removed and replaced where the sidewalk is being removed and replaced (one location). This work shall be incidental to the project. The meter will be removed by the City and installed on the post by City once the post has been reset. The post shall be 54 " long 2" nominal diameter hot dipped galvanized steel schedule 40 with 3/8" weep hole near bottom (ground elevation). Post shall be set 28" behind the curb. The meter post hole shall be cored three (3) inches wide, twelve (12) inches deep.. Meter post hole cores shall be grouted after meter post installation with EUCO ROCK non-shrink grout or approved equal.

.

1.

The Acknowledgement of the Receipt of all Addendums must be printed clearly on the outside of your Bid Package or your Bid may not be opened.