DEPARTMENT OF
PUBLIC WORKS

November 8, 2024

CITY OF JOLIET

ADDENDUM NO. 1

TO: PROSPECTIVE BIDDERS FOR:

CONTRACT NO. 2873-1224
2024 RESURFACING CONTRACT C

THE ATTENTION OF ALL PROSPECTIVE BIDDERS ON THE ABOVE REFERENCED PROJECT IS CALLED TO THE FOLLOWING MODIFICATIONS IN THE CONTRACT DOCUMENTS:

1. Please remove the original Schedule of Prices and replace with the attached Schedule of Prices.
2. Please remove the original Street Listing and replace with the attached Street Listing.

THE ACKNOWLEDGEMENT OF THE RECEIPT OF ALL ADDENDUMS MUST BE PRINTED CLEARLY ON THE OUTSIDE OF YOUR BID PACKAGE OR YOUR BID MAY NOT BE OPENED.



Joseph M. Nordman, P.E.
Roadways Engineer
Phone: (815) 724-3650

17. The undersigned submits herewith his schedule of prices covering the work to be performed under this contract.

CITY OF JOLIET

2024 RESURFACING CONTRACT C

SCHEDULE OF PRICES

(FOR MORE INFORMATION REGARDING THESE ITEMS SEE PLANS AND SPECIFICATIONS)

ITEM #	ITEM DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	COST
1	AGGREGATE BASE COURSE, TYPE B 4"	6,213	SQ YD		
2	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	6,256	TON		
3	LEVELING BINDER, N50	4,216	TON		
4	BITUMINOUS MATERIALS (TACK COAT)	5,588	POUND		
5	DETECTABLE WARNINGS	1,205	SQ FT		
6	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	74,335	SQ YD		
7	DRIVEWAY PAVEMENT REMOVAL	1,935	SQ YD		
8	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	9,595	FOOT		
9	SIDEWALK REMOVAL	37,386	SQ FT		
10	CLASS D PATCHES, 8"	13,356	SQ YD		
11	PARTIAL DEPTH PATCH	1,436	SQ YD		
12	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	39,528	SQ FT		
13	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT, 6"	220	SQ YD		
14	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	1,710	SQ YD		
15	STRUCTURES TO BE ADJUSTED	299	EACH		
16	SANITARY MANHOLES TO BE ADJUSTED	24	EACH		
17	STRUCTURES TO BE RECONSTRUCTED	2	EACH		
18	MANHOLE LIDS	45	EACH		
19	FRAMES AND LIDS	96	EACH		
20	AGGREGATE FOR TEMPORARY ACCESS	76	TON		
21	DETECTOR LOOP REPLACEMENT	180	FOOT		
22	REBUILD EXISTING HANDHOLE	1	EACH		
23	HANDHOLE REMOVAL AND REPLACEMENT	1	EACH		
24	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	260	FOOT		
25	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	272	FOOT		
26	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	50	FOOT		
27	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	59	FOOT		
28	THERMOPLASTIC PAVEMENT MARKING - LINE/SYMBOLS	20	SQ FT		
29	GROOVING FOR RECESSED PAVMENT MARKING 5"	260	FOOT		
30	TEMPORARY PAVEMENT MARKING 4" PAINT	100	FOOT		
31	TEMPORARY PAVEMENT MARKING 24" PAINT	50	FOOT		

32	TEMPORARY PAVEMENT MARKING L & S PAINT	50	SQ FT		
33	TEMPORARY PAVEMENT TAPE R & R	100	FOOT		
34	TREE ROOT PRUNING	80	EACH		
35	LANDSCAPE RESTORATION	3,595	SQ YD		
36	STREETSCAPE BRICK REMOVAL AND REPLACEMENT	210	SQ FT		
37	SUMP LINE CONNECTION TIE IN	2	EACH		
38	TRAFFIC CONTROL AND PROTECTION	1	L SUM		
			BIDDER'S PROPOSAL FOR MAKING THE IMPROVEMENTS		

BIDDER'S EMAIL ADDRESS _____

BIDDER'S PHONE NUMBER(S) _____

Contract C – Street List per Addendum

STREET	FROM	TO	LENGTH	WIDTH
ARCHES DR	MIRAGE AVE	BLISS CT	1128	28
ARCHES COURT	ARCHES DR	NORTH END	315	28
BAZZ DR	SAHARA DR	RUTH FITZGERALD	1032	35
BLISS CT	ADOBE DR	END	410	28
CEDAR BREAKS CT	MIRAGE AVE	END	926	28
CLEARWATER DR	CLEARWATER DR	CREEKSIDE DR	871	28
CREEKSIDE DR	CLEARWATER DR	CLEARWATER DR	1078	28
DISCOVERY DR	TWIN FALLS DR	STONEBRIDGE DR	860	28.5
DISCOVERY DR	FONTANA ST	DESERT DR	1025	28
HARBORSIDE CT	TWIN FALLS DR	END	312	28
HORIZON CT	REFLECTION DR	END	575	28
LANGSFORD LN	STONEBRIDGE DR	DISCOVERY DR	760	35
MOJAVE CT	SIERRA AVE	END	380	28
OCEANSIDE CT	TWIN FALLS DR	END	495	28
REFLECTION CT	HORIZON CT	END	600	28
REFLECTION DR	COUNTY LINE RD	SAHARA AVE	388	35
SAHARA DR	BAZZ DR	TWIN FALLS DR	945	28
SAHARA DR	REFLECTION DR	SAHARA CT	1110	35
SIERRA AVE	DESERT DR	FONTANA	3000	28
SIERRA AVE	MOJAVE	SUPERSTITION CT	540	28
STILLWATER CT	TWIN FALLS DR	END	380	28
STONEBRIDGE DR	LANGSFORD LN	DISCOVERY DR	1378	28
TWIN FALLS DR	OCEANSIDE CT	REFLECTION DR	1305	35
TWIN FALLS DR	MOJAVE DR	VISON AVE	1340	35
TWIN FALLS DR	STILLWATER CT	OCEANSIDE CT	551	28
TWIN FALLS DR	DISCOVERY DR	STILLWATER CT	205	28
TWIN FALLS DR	DISCOVERY DR	BAZZ DR	875	28
BLACKBERRY RIDGE	DRAUDEN RD	WEST END	630	28
CHERRY RIDGE CT	BLACKBERRY RIDGE	SOUTH END	790	29
HOUBOLT RD	JEFFERSON ST	NORTH	180	28.5